



# COLD REALITIES: OVERCOMING CHALLENGES OF WINTER DEWATERING IN ANCHORAGE, ALASKA

**ANMC EMERGENCY SERVICES EXPANSION**

Presented by Alyson Mathers and Emily Helenhouse | May 2026





# Project Overview

- Location: Anchorage, Alaska
- Excavation below water table required continuous dewatering
- Contaminated site (POLs and Chlorinated Solvents) – treatment of excavation dewatering water
- Site history: Gravel mining and asphalt production plant (1960s-1970s)
  
- Dewatering timeline:
  - Design, Verification, and proof of concept testing with excavation water in 2024
  - Start full scale temporary dewatering system and shakedown testing January 2025
  - Decommission 23 temporary dewatering wells (35-45 ft. bgs), pump from basement Foundation sub-drains to temporary system for treatment, Fall 2025
  - Current: Temporary treatment system operation, Design of permanent treatment system and data gap analysis



## Project Overview

- Project: ANMC Emergency Services Expansion
- Location: Anchorage, Alaska
  - 6-story building addition
  - Parking garage
  - Ambulance turnaround
  - Other facilities





## Contaminated Site History

- Site History
  - 19060s-1980s: Material quarry with onsite asphalt production plant
  - 1990s: ANMC constructed
- Identified Contaminants of Concern
  - DRO; RRO; Chloroform; carbon tetrachloride; trichloroethene (TCE); benzene; naphthalene; 1-methylnaphthalene; 1,1,1- and 1,1,2-trichloroethane; 1,1-dichloroethane (1,1-DCA); 1,2-dichloroethane; 2-hexanone; bromodichloromethane; 1,2,3-Trichloropropane; Vinyl Chloride; Ethylene Dibromide; 1,2,3- and 1,2,4-Trichlorobenzene


Block 3, Lots 5A and 8 Tudor Centre  
Hazard ID: 26580  
File No. 2100.38.560






# Dewatering

- Parking Garage and Building Addition Excavation
- 23 dewatering wells to 30-40 feet bgs
- Continuous dewatering and daily monitoring
- Estimated flow rate: 84 gpm
- Average recorded flow rate: 47 gpm from January to April 2025
- Influent Contaminants: DRO, RRO, 1,2,3-TCP
- NO LARGE-SCALE TREATMENT SYSTEMS AVAILABLE LOCALLY





# Timeline



# Groundwater Remediation Plan

- Equipment Considerations
  - Long lead times
  - Limited Local availability
  - High Flow rates
  - COCs
  - GAC Changeout frequency
- Analytical Sampling Considerations
  - COCs, method detection limits – lab selection
  - Turnaround Times
  - GAC changeout frequency
  - Breakthrough and Compliance Monitoring
- Contaminant Plume Migration

- Solutions:
  - Proof of concept – local system with similar EBCT
  - Analytical Sampling Frequency > Estimated Changeout Frequency
  - Field screening (AQR Color-Tec methods, sheen, etc.)
  - Sampling Equipment: Hydrasleeves, Bailers
  - Sampling Locations: Untreated Tank, between GAC Vessels, Treated Tank
  - Sentinel Wells – Groundwater Monitoring

# Step 1: Verification Testing – Proof of Concept

- Contained contaminated dewatering water (Summer/Fall 2024)
  - 10,000 gallons of water with DRO/RRO
  - 5,000 gallons of water with chloroform
- Locally sourced treatment system of smaller scale:
  - Bag filtration unit + 2 x 55gal GAC vessels
  - 10 gpm flow per GAC vessel = 20 gpm flow rate
  - EBCT of 5 minutes = comparable to large scale system
- Treated water below discharge limits, discharge to AWWU system






# Results

				Pre-treatment		Post-treatment	
				Tank 1	Tank 2	Tank 1	Tank 2
Analysis Method	Analyte	ADEC Surface Water Cleanup Level	Unit	Result	Result	Result	Result
AK102	DRO	1.5	mg/L	<b>2.63</b>	<b>&lt;0.22</b>	<b>0.21</b>	<b>&lt;0.20</b>
AK103	RRO	1.1	mg/L	<b>2.21</b>	<0.24	<b>&lt;0.62</b>	<0.21
8260D	Chloroform	2.2	µg/L	<0.310	<b>9.5</b>	<0.030	<0.030



# Full-Scale System Design

- Full-scale temporary system components in a temporary, enclosed, heated space
  - Two 18,000 baffle tanks for influent and treated effluent
  - Bag filtration units for turbidity management
  - Two large GAC vessels
  - Blast heating, insulation blankets




## Step 2: Verification Testing – Full Scale System

- Full Scale System
- Treat 18,000 gallons from dewatering wells
- Contaminants below maximum discharge values
- Recycled to reduce turbidity to less than maximum discharge values
  - New GAC = high initial turbidity



# Shakedown Testing

- Increased sample frequency – First 2 weeks of operation
  - Analytical samples (GRO/DRO/RR0/VOC) every two days
  - Hourly field screening: pH and turbidity until stabilization
  - Groundwater sampling of accessible dewatering wells
  - Slow startup due to cold temps, troubleshooting system
    - Heated blankets
    - Thawing dewatering wells





# Monitoring and Compliance

- Daily monitoring of treated effluent water
- Weekly monitoring of the stormwater outlet
- Weekly analytical sampling
  - Influent groundwater
  - Between lead and lag GAC vessels
  - Treated effluent
- Sentinel wells installed between known contamination zones and dewatering wells
  - Sampled weekly with hydrasleeves for increased flexibility and reduced volatile disturbance





NAEP Conference | May 2026






# CHALLENGES IN ALASKA






# Climate



Accumulated Precipitation, 2024 and 2025




Daily Temperature, 2025



# Groundwater elevation

Sentinel Well W24-WELL-02P



# Winter Weather: Challenges

- Subfreezing temps
- Snow and ice accumulation
  - locating wells, ice in annular space
- Wind storms (>80 mph in December 2024)
  - Equipment loss/Damage
- Heating for dewatering treatment system
- Winter rain, freeze and thaw cycles
  - Impacts on excavation flooding, flow rates, and sediment loads



# Winter Weather: Solutions

- Shelter upgrade
  - Tent to Connex
- Larger Capacity Bag Filter System
- Heaters
- Heat Trace
- Insulation blankets
- Blow torches
- Ice Chippers and Shovels
- Safety vests
- Field Check Ins



# Lead Times, Delays

- Equipment
- Materials (Barge)
- Analytical Results
  
- Solutions
  - Field Screening
    - AQR Color-Tec
  - RUSH turnaround times
  - Preorder materials and equipment
  - Weekly review of supply stock



# Accessibility and Safety

- Tight construction site, limited free space
- Multiple heavy equipment in operation
- Uneven ground – excavation, ice
  
- Solutions
  - Boot grips
  - Sampling in Pairs
  - Daily coordination with contractors
  - Walkie-Talkie radios, hand signals



wsp

THANK  
YOU

wsp.com

